

PARISH OF NATCHITOCHEs
REQUEST FOR PROPOSALS FOR
PULVERIZATION OF SELECTED ROADWAY SEGMENTS IN PARISH SYSTEM
SEPTEMBER 28, 2020
PAGE 1-OF-3

This is a Request for Proposals for the pulverization of selected roadway segments in the Parish highway system.

Location of Work

The specific roadway segments, and the approximate total length and width to be pulverized on each, are as follows:

Albritton Road – 3,380 linear feet @ approx. width of 16 feet = 6,008.9 Square Yards
Bumgarner Road – 1 mile @ approx. width of 16 feet = 9,386.7 Square Yards
Central Loop – 6,970 linear feet @ approx. width of 18 feet = 13,940.0 Square Yards
Central Street – 3,500 linear feet @ approx. width of 16 feet = 6,222.2 Square Yards
Clark Loop – 4,800 linear feet @ approx. width of 16 feet = 8,533.3 Square Yards
Freeman Loop – 7,970 linear feet @ approx. width of 16 feet = 14,168.9 Square Yards
Goldonna Road – 3 miles @ approx. width of 18 feet = 31,680.0 Square Yards
Government Road – 3 miles @ approx. width of 18 feet = 31,680.0 Square Yards
Hart Road – 3 miles @ approx. width of 18 feet = 31,680.0 Square Yards
Janie-Gorum Road – 1 mile @ approx. width of 16 feet = 9,386.7 Square Yards
Lake Gorum Road – 3 miles @ approx. width of 16 feet = 28,160.0 Square Yards
Mathis Road – 1,500 linear feet @ approx. width of 16 feet = 2,666.7 Square Yards
Rawls Loop – 4,200 linear feet @ approx. width of 16 feet = 7,466.7 Square Yards
Total Estimated Area to be Pulverized = 200,980.1 Square Yards

Note 1: Several listed roads will not be pulverized for their entire length.

Note 2: For roads where only selected segments will be pulverized, these segments are not necessarily contiguous. The specific areas to be pulverized on these roads will be marked by Parish representatives.

RFP FOR PULVERIZATION OF SELECTED ROADWAY SEGMENTS IN PARISH SYSTEM

SEPTEMBER 28, 2020

PAGE 2-OF-3

Note 3: The figures shown above are estimates only. Payment will be based on the actual dimensions where pulverization work is performed.

Scope of Work

The work shall consist of pulverizing the entire depth of existing asphalt surfacing, and the top 1 to 2 inches of the existing raw aggregate or soil cement base course. Equipment to be utilized shall be a soil stabilizer or milling machine, producing maximum size particles not exceeding approximately 1.5 inches. Blading by motor grader and compaction with a steel-wheel or pneumatic roller shall follow the pulverization operation, so as to produce an aggregate-surfaced roadway that can be readily traversed by vehicles and effectively maintained by Parish forces. Pulverization, blading, and compaction shall be to the satisfaction of the Director of Public Works.

No direct payment shall be made for mobilization and de-mobilization, temporary traffic control, construction layout, or other incidental work.

Through and local traffic shall be maintained on all roadway segments for the duration of the work. Contractor shall utilize flaggers and advance warning signs [moving operation] as needed.

Submittal of Proposals, Bonds and Insurance Requirements, and Prosecution and Progress of the Work

Written proposals for this work shall be submitted to Mrs. Cathy Creamer, Parish Purchasing Agent, whose office is located in Suite 304 of the Live Oak Building located at 203 St. Denis Street, Natchitoches, LA 71457, or by e-mail to ccreammer@npgov.org. **Deadline for submittal is 10:00 a.m. on Monday, October 12, 2020.**

Proposers must possess a current license issued by the State of Louisiana Contractors Licensing Board in road construction or a related area acceptable to the Parish President.

A Proposal submittal shall consist of completion of the attached returnable entitled, "Summary of Estimated Quantities and Proposed Unit Prices," with a proposed unit price indicated for the work. **Note that the proposed unit price for each road segment must be identical, otherwise the proposal will be rejected by the Parish of Natchitoches.**

The Parish of Natchitoches reserves the right to reduce the overall amount of work to be completed under this contract by applying the proposed unit price to only selected roads, so as to result in a total contract amount that fits within the statutory bid limit and the available project budget.

RFP FOR PULVERIZATION OF SELECTED ROADWAY SEGMENTS IN PARISH SYSTEM

SEPTEMBER 29, 2020

PAGE 3-OF-3

Upon written notification of acceptance of proposal by the Parish, the contractor shall furnish within seven (7) calendar days payment and performance bonds in an amount equal to the total proposed price for the work, along with a certificate of liability insurance in the amount of \$1,000,000 naming the Parish of Natchitoches as an additional insured. A Notice to Proceed shall be issued requiring work to begin within twenty-one (21) calendar days of notification of acceptance of proposal.

Upon initiation of operations, the contractor shall prosecute all work to its timely completion without de-mobilizing from the project site. All work shall be completed and ready for final acceptance within **thirty (30) calendar days, exclusive of adverse weather days. Unless it is the result of factors beyond the contractor's control, failure to complete work on time shall result in assessment of a \$270 per calendar day charge for stipulated damages.**

Upon completion of the work and final acceptance by the Parish, the contractor shall submit an itemized invoice to Mrs. Julie Lockhart, Parish Treasurer, for payment.

Questions about this RFP may be directed to Mr. Nick Verret, Parish Engineer, at (318) 451-1727, or by e-mail to nverret@npgov.org.

END OF RFP

**PROPOSAL RETURNABLE
PULVERIZATION OF SELECTED ROADS IN NATCHITOCHE PARISH SYSTEM
SUMMARY OF ESTIMATED QUANTITIES AND PROPOSED UNIT PRICES**

SEPTEMBER 28, 2020

ITEM NO.	DESCRIPTION	EST. QUANTITY	UNIT	PROPOSED UNIT PRICE *	EXTENDED PRICE
01	Pulverization of Albritton Road	6,008.9	SQ YD		
02	Pulverization of Bumgarner Road	9,386.7	SQ YD		
03	Pulverization of Central Loop	13,940.0	SQ YD		
04	Pulverization of Central Street	6,222.2	SQ YD		
05	Pulverization of Clark Loop	8,533.3	SQ YD		
06	Pulverization of Freeman Loop	14,168.9	SQ YD		
07	Pulverization of Goldonna Road	31,680.0	SQ YD		
08	Pulverization of Government Road	31,680.0	SQ YD		
09	Pulverization of Hart Road	31,680.0	SQ YD		
10	Pulverization of Janie-Gorum Road	9,386.7	SQ YD		
11	Pulverization of Lake Gorum Road	28,160.0	SQ YD		
12	Pulverization of Mathis Road	2,666.7	SQ YD		
13	Pulverization of Rawls Loop	7,466.7	SQ YD		
TOTAL PROPOSED PRICE				\$	

* NOTE: PROPOSED UNIT PRICE MUST BE THE SAME FOR ALL LISTED ROADS. FAILURE TO DO SO WILL RESULT IN REJECTION OF PROPOSAL.

SUBMITTED BY: _____

COMPANY NAME & LA LICENSE NUMBER: _____

AUTHORIZED REPRESENTATIVE SIGNATURE: _____

PHONE: _____ E-MAIL: _____

DATE: _____